




C1 PLAN DETAIL
3' = 1'-0"



E1 COLUMN CAP DETAIL
1 1/2" = 1'-0"
• COLUMN LINES 1C, 1D, 1E, 4C, 4D, AND 4E



G1 COLUMN CAP SECTION
1 1/2" = 1'-0"



J1 COLUMN CAP DETAIL
1 1/2" = 1'-0"
• COLUMN LINES 4B AND 4F

10700 NOTE:
CANOPY AS MANUFACTURED BY 'AVADEK' OR APPROVED EQUAL -- CONTRACTOR TO VERIFY ALL MOUNTING REQUIREMENTS

09600 NOTE:
PROVIDE A 45000 ALLOWANCE FOR CENTER COURT LOGO

11400 NOTE:
CONTRACTOR RESPONSIBLE FOR REMOVAL, STORING AND RE-INSTALLATION OF EXISTING SCOREBOARD. VERIFY LOCATION WITH OWNER PRIOR TO INSTALLATION

03010 NOTE:
RECESSED CONC. FLOORING BELOW WOOD GYM FLOORING SHALL BE LEVEL TO WITHIN 1/8" IN 10'-0" EACH DIRECTION

10700 NOTE:
CANOPY AS MANUFACTURED BY 'AVADEK' OR APPROVED EQUAL -- CONTRACTOR TO VERIFY ALL MOUNTING REQUIREMENTS

EXISTING BUILDING TO REMAIN

10700 NOTE:
CANOPY AS MANUFACTURED BY 'AVADEK' OR APPROVED EQUAL -- CONTRACTOR TO VERIFY ALL MOUNTING REQUIREMENTS

03010 NOTE:
RECESSED CONC. FLOORING BELOW WOOD GYM FLOORING SHALL BE LEVEL TO WITHIN 1/8" IN 10'-0" EACH DIRECTION


10700 NOTE:
CANOPY AS MANUFACTURED BY 'AVADEK' OR APPROVED EQUAL -- CONTRACTOR TO VERIFY ALL MOUNTING REQUIREMENTS

GENERAL NOTES

- A. PLAN DIMENSIONS ARE TO FACE OF STUD OR FACE OF MASONRY
- B. REFER TO SPECIFICATION SECTION 08000 FOR DOOR FRAME AND HARDWARE SCHEDULE
- C. REFER TO SPECIFICATION SECTION 09000 FOR ROOM FINISH SCHEDULE
- WALL SCHEDULE**
- METAL STUD WALL WITH 3/8" TYPE 'X' GYPSUM BOARD EACH SIDE EXPOSED TO VIEW - - PROVIDE "MR." GYPSUM BOARD at "WET WALLS"
- CONCRETE MASONRY UNIT WALL
- FULL HEIGHT ONE HOUR FIRE PARTITION WITH METAL STUD AND ONE LAYER 3/8" TYPE "X" GYPSUM BOARD EACH SIDE FOLLOW U.L. DESIGN 1425
- FULL HEIGHT NON-RATED WALL WITH METAL STUD AND ONE LAYER 3/8" TYPE "X" GYPSUM BOARD EACH SIDE

NUMBERED NOTES

- DIV. 4 - MASONRY**
- 04205 8" THROUGH COLOR CMU TYPE 1- 9" MOOTHFACE
- 04218 8" CMU BOND BEAM WITH 2 CONTINUOUS #5 BARS - GROUT FULL
- DIV. 6 - WOOD**
- 06404 3/4" HARDWOOD VENEERED PLYWOOD WITH MATCHING EDGE BAND
- DIV. 7 - THERMAL + MOISTURE PROTECTION**
- 07240 EXTERIOR INSULATION AND FINISH SYSTEM (EIFS)
- 07240 EXTERIOR INSULATION AND FINISH SYSTEM (EIFS)
- 07241 2" MOLDED EXPANDED POLYSTYRENE INSULATION BOARD
- 07245 SANDBLAST TEXTURE APPLIED OVER MANUFACTURER'S REINFORCING MESH EMBEDDED IN BASE COAT
- 07900 TWO PART POLYURETHANE ELASTOMERIC SEALANT WITH BACKER ROD AS REQUIRED
- DIV. 8 - DOORS AND WINDOWS**
- 08105 3" WIDE x 8'-0" LONG FLAT ALUMINUM THRESHOLD - FIELD TRIM AS REQUIRED TO FIT OPENING AND COVER 1" EXPANSION JOINT AT RESILIENT WOOD SPORTS FLOORING -- FURNISHED BY 08115 CONTRACTOR and INSTALLED BY 03530 CONTRACTOR
- DIV. 9 - FINISHES**
- 09260 3/8" x 25 GAUGE METAL STUD AT 1'-4"
- 09268 DOUBLE STUDS OF MATCHING GAUGE BUT NOT LESS THAN 20 GA.
- 09274 1/2" GLASS MATT EXTERIOR GYPSUM SHEATHING
- 09645 BASKETBALL COURT STRIPING
- 09646 3'-0" WIDE BORDER
- 09901 IP8-3 (FERROUS METAL - - HIGH GLOSS)
- 09903 IP8-5 (PAINTED WOOD - GLOSS FINISH)
- 09911 IP8-7 (PAINTED CMU - SEMI GLOSS FINISH)
- DIV. 10 - SPECIALTIES**
- 10510 RECESSED MOUNTED FIRE EXTINGUISHER CABINET WITH 5 LB. "ABC" FIRE EXTINGUISHER
- 10522 SURFACED MOUNTED 5 LBS. "ABC" FIRE EXTINGUISHER
- DIV. 11 - EQUIPMENT**
- 11484 BASKETBALL BACKSTOP EQ. TO "FORTE" 90349 SERIES x FORWARD FOLD SINGLE MAST, REAR BRACED WITH 1208-0000 GLASS BACKBOARD, BOLT ON FOLDING, ULTRA FLEX GOAL, FOLIER OPERATION and ELECTRIC HEIGHT ADJUST
- DIV. 12 - FURNISHINGS**
- 12160 ELECTRIC TELESCOPING SEATING
- DIV. 13 - SPECIAL CONSTRUCTION**
- 13120 CLEAR SPAN PRE-ENGINEERED STRUCTURE WITH TAPERED COLUMNS AS DESIGNED BY 13120 MANUFACTURER
- 13140 METAL BUILDING CONTRACTOR SHALL PROVIDE INTERMEDIATE SUPPORTS AT ROOF TO SUPPORT (6) BASKETBALL GOALS



CADCO
ARCHITECTS - ENGINEERS, INC.
2401 S. WILLIS, STE. 200 ABILENE, TEXAS 79605

NEW PRACTICE GYM and VO-TECH FACILITY
RANKIN I.S.D.
RANKIN, TEXAS

PROJECT NUMBER A641
AUGUST 31, 2015

A101

M4 PRACTICE GYM FLOOR PLAN at 14,394 gross square feet
3/32" = 1'-0"

